



- NOTES: 1. SEABROOK ISLAND RD. TO BE REDUCED TO ONE LANE AS SHOWN FOR APPROX. 3-4 WEEKS FOR ROAD WORK & NEW ENTRANCE CONSTRUCTION.  
 2. REF. WORK ZONE TRAFFIC CONTROL PROCEDURES DRAWING NO. 405-01-A FOR SIGN & DEVICE SPACINGS. POSTED SPEED LIMIT IS 35 MPH.  
 3. FLAGGERS SHALL WEAR CLASS 3 HIGH VISIBILITY SAFETY APPAREL MEETING ANSI/ISEA 107 REQUIREMENTS.  
 4. FLAGGER STATIONS SHALL BE ILLUMINATED BY THE USE OF PORTABLE LIGHT TOWERS.  
 5. MUST MAINTAIN A 10 FT. MIN. LANE WIDTH IN OPEN TRAFFIC LANE AT ALL TIMES.  
 6. NO WORK PERMITTED BETWEEN 6 AM - 8 PM.  
 7. ALL MATERIALS SHALL MEET OR EXCEED SCDOT SPECIFICATIONS.



Project Name <b>KIAWAH SENIOR LYING</b>		
Prime Contractor <b>J.H. HIERS CONSTRUCTION</b>	Traffic Control Contractor <b>B.C. CANNON CO.</b>	
Phone <b>864-235-1255</b>	Sheet Number <b>1</b>	Date <b>10-11-21</b>
Prepared By <b>TIM TAYLOR</b>	<b>N.T.S.</b>	